1. Make sure the subfloor is structurally sound, level and is free of dust and debris.
2. Check for protruding nails and/or defects in the subfloor. If installing over concrete, the concrete must be dry with moisture emission rates that do not exceed <b>3 lbs. per 1000 square feet per 24 hours</b> as measured by the <b>Anhydrous Calcium Chloride Test</b> .
1. Start in a corner with the tape strip side next to the wall and the overlapping film toward the open room.
2. Install <b>ComboFoam®</b> parallel to the wall in the opposite direction that you plan to install the flooring planks.
3. When installing the ComboFoam®, leave at least 2″ going up the wall.
1. Roll out the next roll of <b>ComboFoam®</b> in the same manner, making sure that the foam seams are butted together.
2. Be sure to overlap only the moisture barrier lip and not the foam pad.
1. <b>Remove the adhesive liner</b> and adhere the foam to the film overlap.
1. Install the flooring per manufacturer's instructions.

## comboFoam®





